



NOTES:

1. All concrete shall comply in all respects with NZS 3109, and to be 30MPa crushing strength after 28 days minimum.
2. All surfaces to have a broom finish.
3. A full bitumen coat completely covering the surface and extending up the sides of the reinstatement, is to be applied prior to the laying of the M15 asphaltic concrete.
4. The surface shall be sealed with a 50mm depth M15 asphaltic concrete, 300mm in front of kerb and channel.
5. Height from channel invert to string line to be between 150mm and 300mm.
6. Existing footpath is to be sawcut. The minimum distance between the edge of the new vehicle crossing and an existing construction joint is 1.0m. It may be necessary to renew at least 1.0m of footpath either side of the vehicle crossing to achieve this.

	INITIALS	DATE	 Manawatu District Council <small>INFRASTRUCTURE SHARED SERVICES</small>  Roadworks <small>CONSTRUCTION</small>	Stamp Status 6182-C		
DESIGN	M.T.	13/08/13		Scale DO NOTSCALE		
DRAWN	C.R.	13/08/13		Drawing No.	Sheet No.	Rev.
CHECKED	M.T.	13/08/13		1	23.6	A
APPROVED	W.K.	10/03/14		COMMERCIAL / INDUSTRIAL VEHICLE CROSSING		